

Lampiran Pengumuman:	681.1.Peng/SCM/PLN-NPS/2024
Tanggal	:11 Juni 2024

BILL OF QUANTITY (BOQ)

AI 2023 - Program Keandalan Unit PLTU Bolok Penggantian Debris (Casing, Strainer, Gearbox) Condensor Unit 1 (WO95459)

No	ITEM BARANG/JASA	Jumlah	Satuan
1.	HOUSING, BODY DEBRIS FILTER SET, TYPE FILTER: XGD-700, OUTER SHELL CARBON STEEL, LINED WITH RUBBER, INTERNAL FILTER AND SEWAGE SYSTEM 316L, DESIGN PRESS: 0.6MPA, DESIGN TEMP: 90 DEG C, WORK PRESS: 0.3 MPA, WORK TEMP: 50 DEG C, (INCLUDING EXTERNAL REDUCER), MANUFACTURE: LIANYUNGANG XINGANG POWER AUXILIARY MACHINERY CO.LTD	2	Set
2.	Jasa pemasangan a. Melakukan Site survey untuk memastikan dimensi, fungsi dan debris b. Pembuatan Detail Engineering Design (DED) c. Pembongkaran Debris Lama (2 set) d. Pemasangan Debris Baru (2 set) e. Pengujian f. Commisioning	1	Lot